

EXTREME
WALL PANEL

FIELD INSTALLED
PANEL SILL PLATE

CONTINUOUS $\frac{3}{8}$ "
& $\frac{1}{2}$ " PANEL
SEALANT

$\frac{1}{2}$ " SCREWS @ 8"
O.C. OR 2"-8d
NAILS @ 6" O.C.
FASTENED ON EACH
SIDE (U.N.O.)

ANCHOR BOLTS
PLACED PER CODE

PANEL SCREWS W/
WASHERS @ 24" O.C.
W/ MINIMUM $\frac{1}{4}$ "
PENETRATION INTO SILL
PLATE (U.N.O.)

OPTIONAL PANEL SCREWS

MIN. $\frac{7}{16}$ " UNDERLAYMENT
PERPENDICULAR TO
PANEL SEAMS

EXTREME FLOOR PANEL

ADDITIONAL 2x BLOCKING
AT STRUCTURAL MEMBER
IN WALL

DOUBLE TREATED 2x SILL
PLATE ATTACHED
TOGETHER W/ 3" CONST.
LAGS @ 24" O.C. OR 16d
NAILS @ 12" O.C. IN 2
ROWS STAGGERED (U.N.O.)
W/ PANEL SEALANT
BETWEEN 2x's

SILL SEALER
CONCRETE OR
MASONRY FOUNDATION

SECTION
NOT TO SCALE

DETAIL TITLE : PANEL FLOOR BLOCKING

DETAIL NO. : EP-209

PAGE NO. : 2 - 9

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS