

Construction Detail Manual

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

SIPs Done Right!
800.977.2635
extremepanel.com



**Structural Insulated
Panel Association**

TABLE OF CONTENTS

TOOLS & MISCELLANEOUS ITEMS.....	PAGE 1
TYPES OF CONNECTIONS.....	PAGE 2
INSTALLATION REQUIREMENTS & GUIDELINES.....	PAGE 3-4
ELECTRICAL INSTALLATION HINTS.....	PAGE 5

SECTION 1 - GENERAL DETAILS

EP-101	BUILDING SECTION.....	PAGE 1 - 1
EP-102	BUILDING SECTION.....	PAGE 1 - 2
EP-103	BLOCK SPLINE CONNECTION.....	PAGE 1 - 3
EP-104	I-JOIST SPLINE CONNECTION.....	PAGE 1 - 4
EP-105	DOUBLE 2x LUMBER CONNECTION.....	PAGE 1 - 5
EP-106	PLYWOOD SPLINE CONNECTION.....	PAGE 1 - 6
EP-107	BLOCK SPLINE (VAPOR BARRIER).....	PAGE 1 - 7
EP-108	SPLINE FASTENED AT TOP ONLY.....	PAGE 1 - 8
EP-109	PANEL TO STEEL CONNECTION.....	PAGE 1 - 9
EP-110	TOP AND SILL PLATE CONNECTIONS.....	PAGE 1 - 10
EP-111	TOP SHIM PLATE CONNECTION.....	PAGE 1 - 11
EP-112	BUTT CORNER CONNECTION.....	PAGE 1 - 12
EP-113	FLY-BY CORNER CONNECTION.....	PAGE 1 - 13
EP-114	ANGLED CORNER CONNECTION.....	PAGE 1 - 14
EP-115	TIMBER FRAME MEMBER CONNECTION.....	PAGE 1 - 15
EP-116	TIMBER FRAME CORNER CONNECTION.....	PAGE 1 - 16
EP-117	TIMBER FRAME MEMBER CONNECTION.....	PAGE 1 - 17
EP-118	TIMBER FRAME MEMBER CONNECTION.....	PAGE 1 - 18
EP-119	STRUCTURAL INSULATED RIM BOARD.....	PAGE 1 - 19
EP-120	LEDGER ATTACHMENT.....	PAGE 1 - 20
EP-121	SILL PLATE PLACEMENT.....	PAGE 1 - 21
EP-122	WIND BRACING TIPS.....	PAGE 1 - 22

SECTION 2 - FLOOR / FOUNDATION DETAILS

EP-201	TREATED BASE PLATE.....	PAGE 2 - 1
EP-202	TREATED SILL PLATE.....	PAGE 2 - 2
EP-203	PANEL TO FOUNDATION CONNECTION.....	PAGE 2 - 3
EP-204	FOUNDATION FRAMING.....	PAGE 2 - 4
EP-205	INSULATED RIM BOARD CONNECTION.....	PAGE 2 - 5
EP-206	TOP CHORD BEARING FLOOR TRUSS.....	PAGE 2 - 6

EP-207	HANGING FLOOR SYSTEM.....	PAGE 2 - 7
EP-208	PANEL FLOOR TO FOUNDATION.....	PAGE 2 - 8
EP-209	PANEL FLOOR BLOCKING.....	PAGE 2 - 9
EP-210	PANEL FLOOR BLOCKING.....	PAGE 2 - 10
EP-211	HOLDDOWN CONNECTION.....	PAGE 2 - 11
EP-212	STRAP HOLDDOWN CONNECTION.....	PAGE 2 - 12
EP-213	BRACING FOR OPEN WEB FLOORING.....	PAGE 2 - 13

SECTION 3 - WALL DETAILS

EP-301	TYPICAL PANEL WALL.....	PAGE 3 - 1
EP-302	TYPICAL WINDOW OPENING.....	PAGE 3 - 2
EP-303	DOUBLE BUCK WINDOW OPENING.....	PAGE 3 - 3
EP-304A	HEADERED WINDOW OPENING.....	PAGE 3 - 4A
EP-304B	INSUL-BEAM II HEADERED OPENING.....	PAGE 3 - 4B
EP-305	ROOF TRUSS BEARING.....	PAGE 3 - 5
EP-306	ELECTRICAL CHASES.....	PAGE 3 - 6
EP-307	ELECTRICAL CHASES.....	PAGE 3 - 7
EP-308	ELECTRICAL BOX INSTALLATION.....	PAGE 3 - 8
EP-309	ELECTRICAL DOOR CHASES.....	PAGE 3 - 9
EP-310	INTERIOR WALL TO PANEL CONNECTION.....	PAGE 3 - 10
EP-311	TYPICAL CABINET CONNECTION.....	PAGE 3 - 11
EP-312	ISLAND VENT INSTALLATION.....	PAGE 3 - 12

SECTION 4 - ROOF DETAILS

EP-401	BUILT-UP 2x WEDGE.....	PAGE 4 - 1
EP-402	BEVELED TOP PLATE.....	PAGE 4 - 2
EP-403	L-SHAPED 2x WEDGE.....	PAGE 4 - 3
EP-404	ROOF TO ICF CONNECTION.....	PAGE 4 - 4
EP-405	FLUSH FOAM RIDGE.....	PAGE 4 - 5
EP-406	ROOF WEDGE.....	PAGE 4 - 6
EP-407	12:12 PITCH RIDGE.....	PAGE 4 - 7
EP-408	ROOF VALLEY (FLUSH FOAM).....	PAGE 4 - 8
EP-409	ROOF VALLEY (LUMBER CONNECTION).....	PAGE 4 - 9
EP-410	ROOF VALLEY (OVERLAY).....	PAGE 4 - 10
EP-411	ROOF VALLEY (LUMBER CONNECTION).....	PAGE 4 - 11
EP-412	ROOF HIP (FLUSH FOAM).....	PAGE 4 - 12
EP-413	ROOF HIP (LUMBER CONNECTION).....	PAGE 4 - 13
EP-414	FULL PANEL OVERHANG (SQUARE CUT).....	PAGE 4 - 14
EP-415	FULL PANEL OVERHANG (PLUMB CUT).....	PAGE 4 - 15
EP-416	FULL PANEL OVERHANG (OPTIONAL).....	PAGE 4 - 16
EP-417	FULL PANEL RAKE OVERHANG.....	PAGE 4 - 17
EP-418	RAFTER TAIL EAVE.....	PAGE 4 - 18

EP-419	RAFTER TAIL RAKE	PAGE 4 - 19
EP-420	RAFTER TAIL (OPTIONAL)	PAGE 4 - 20
EP-421	PARAPET WALL	PAGE 4 - 21
EP-422	ROOF LEDGER	PAGE 4 - 22
EP-423	ROOF PENETRATIONS	PAGE 4 - 23
EP-424	ROOF / FLOOR OPENINGS	PAGE 4 - 24
EP-425	ROOF PANEL CONNECTIONS	PAGE 4 - 25
EP-426	ROOF / FLOOR FASTENING PATTERNS	PAGE 4 - 26

SECTION 5 - SUPPLEMENTAL INSERTS

INSTRUCTIONS FOR APPLYING TWO-PART EXPANDING
FOAM SEALANT

TWO-PART EXPANDING FOAM KIT OPERATING INSTRUCTIONS

OPTIONAL CTX CONTRUCTION LAG SCREW LETTER

TOOLS & MISCELLANEOUS ITEMS NEEDED FOR CONSTRUCTION

1 ½" SCREWS (#8 OR #9)
3" CONSTRUCTION LAGS OR #9 x 3" SCREWS
MINIMAL EXPANDING FOAM & FOAM GUN
PANEL SEALANT
CAULKING GUN (20 oz. SAUSAGE PACK STYLE)
ELECTRIC FOAM CUTTER
JIMMY'S STRAP JACK PANEL PULLER
OR 2" NYLON LOAD STRAP (WITH FLAT HOOK)
LIFTING PLATES FOR ROOF & TALL WALL PANELS
PRE-CUT TREATED BOTTOM PLATE FOR WIDTH

¾" DRILL OR IMPACT DRIVER (CORDLESS)
½" DRILL (FOR LONG PANEL SCREWS)
CIRCULAR SAW
RECIPROCATING SAW (6" & 12" BLADES)
1 ¼" OR 1 ½" CHIPPER BIT (FOR ELECTRICAL CHASE THROUGH PLATES)
T25 & T30 TORX DRIVER BIT
4'-0" LEVEL
CHALK LINE
SLEDGE HAMMER
HARD WOOD BLOCK (APPROXIMATELY 8" x 12")
DRILL BIT FOR ANCHOR HOLES IN BOTTOM PLATE
HAMMER

NOTE: ANY BUILDING SIDEWALL THAT HAS 60'-0" OR MORE WITH NO PARTITIONS MUST HAVE PROPER BRACING FROM RAFTER TO SIDEWALL FOR STRUCTURAL STRENGTH.

EXAMPLE: SPECIAL TRUSS CONNECTIONS, KNEE BRACING, PARTITION WALL, OR TEMPORARY BRACING UNTIL SUCH BRACING IS COMPLETED.


MATERIAL TERMS IN GUIDE DETAILS VS. ACTUAL ITEMS SENT

1 ½" SCREWS (#8 OR #9)
3" CONST. LAGS
*(16d NAILS @ 12" O.C.
IN 2 ROWS STAGGERED
CAN BE USED-BY OTHER)*


PANEL SCREWS
PANEL SEALANT
SIP TAPE

1 ½" BTX SCREWS (ACQ APPROVED)
3" CTX CONSTRUCTION LAG SCREWS
TYP-24" O.C. IN 2 ROWS STAGGERED
#9X3" BTX SCREWS AS REQUESTED
TYP-12" O.C. IN 2 ROWS STAGGERED
TRUFAST PANEL SCREWS
SIP-SEAL ADHESIVE SEALANT
SIP-SEAL VAPOR TAPE


THE "TYPES" OF CONNECTIONS USED ON DETAILS




TYPE 3:
SPECIAL SETBACK = S




TYPE 4:
SPECIAL SETBACK = S




TYPE 6:
BLOCK SPLINE
I-JOIST SPLINE
2x LUMBER SPLINE



TYPE 5:
PLYWOOD SPLINE



TYPE 1:
RIGHT FLANGE



TYPE 2:
LEFT FLANGE

NOTE: WALL TYPE 5, 1, & 2 ARE OPTIONAL AND ARE
ONLY USED IN SPECIAL SITUATIONS

LICENSE EXTREME PANELS IS A LICENSEE OF PREMIER BUILDING SYSTEMS (PBS). ALL PANELS ARE MANUFACTURED PER PBS STANDARDS AND TESTING.

FOAM CORE EXTREME PANELS USE EXPANDED POLYSTYRENE (EPS) FOAM INSULATION AS THE EXTREME PANEL CORE. EPS OFFERS AN INSULATION VALUE OF APPROXIMATELY R-4 PER INCH. PANELS ARE AVAILABLE WITH FOAM THICKNESS OF 3 5/8", 5 5/8", 7 3/8", 9 3/8", AND 11 3/8", WITH PANEL INSULATING VALUES RANGING FROM R-14 TO R-48. EPS DOES NOT CONTAIN ANY FORMALDEHYDE OR OZONE-DEPLETING CFC'S.

BUILDING CODE REPORTS REFER TO THE FOLLOWING CODE REPORTS (AVAILABLE FROM YOUR MANUFACTURER) FOR DETAILED INFORMATION ABOUT EXTREME PANEL / PREMIER PANEL PROPERTIES AND TEST PERFORMANCE:

NTA - LISTING REPORT: PRS032808-3
NTA DOES 3rd PARTY INSPECTION FOR QUALITY CONTROL

ICC-ES REPORT - ESR-1882
UL CLASSIFIED - MFRS. REF. NO. R14340

IMPORTANT INSTALLATION REQUIREMENTS FOR PROPER PERFORMANCE AND SAFETY WITH PANELS, THE FOLLOWING MINIMUM GUIDELINES MUST BE FOLLOWED:

* STORAGE AND HANDLING OF PANELS PANELS SHOULD BE KEPT DRY DURING STORAGE. KEEP STACKED OFF THE GROUND ON LEVEL BLOCKING TO PREVENT WARPING & TWISTING.

* SEALING EXTERIOR SKINS OF ROOF AND FLOOR PANELS ALL EXPOSED PANEL SEAMS NEED TO BE SEALED WITH PANEL SEALANT.

* VAPOR BARRIER MUST BE USED IF PANELS ARE BEING APPLIED OVER TIMBER FRAME OR OTHER STRUCTURE THAT ALREADY HAS TONGUE AND GROOVE LUMBER OR GYPSUM BOARD APPLIED.

* SEALING BETWEEN PANELS ALL PANEL JOINTS MAY BE SEALED WITH PANEL SEALANT TO BLOCK MOISTURE / AIR MOVEMENT THROUGH THE PANELS. PROPER SEALING IS EXTREMELY IMPORTANT. REFER TO GUIDELINES IN THIS MANUAL FOR PROPER TECHNIQUES.

* ASSEMBLY EXTREME PANELS ARE CAREFULLY ENGINEERED FOR STRENGTH AND DURABILITY. TO BENEFIT FULLY FROM THE PANEL STRENGTH, PANELS MUST BE PROPERLY SECURED TO EACH OTHER. SECURE PANELS FIRMLY AT ALL JOINTS AND INTERSECTIONS USING THE DETAILS FOUND IN THIS MANUAL. ATTACH PANELS FIRMLY TO ALL DIMENSIONAL LUMBER WHICH THEY CONTACT USING PANEL SEALANT AND FASTENERS. FOLLOW FASTENER SIZE, LENGTH, AND ON-CENTER SPACING REQUIREMENTS LISTED IN THIS MANUAL PRECISELY. SPECIAL LOADING SITUATIONS MAY REQUIRE ADDITIONAL ENGINEERING, REVIEW, AND CONSIDERATION.

* HOISTING PANELS PANELS CAN BE HOISTED ONTO THE ROOF USING VARIOUS METHODS. WHEN USING A CRANE, MAKE SURE THE CRANE OPERATOR IS SKILLED IN THIS KIND OF WORK. THE MOST EFFECTIVE AND SIMPLEST WAY TO HOLD THE PANELS IS TO USE STEEL PLATES BOLTED THROUGH THE PANEL. THE STEEL PLATES ARE SECURED WITH STRAPS TO THE CABLE FROM THE CRANE. BEFORE HOISTING, FASTEN A SERIES OF 2x4s TO THE TOP FACE OF THE PANEL, USING AT LEAST #9x3" SCREWS 12" O.C. TO SERVE AS FOOT HOLDS ONCE THE PANEL IS ON THE ROOF. NEVER LET ANYONE BE UNDER THE PANEL AS IT IS BEING LIFTED.

INSTALLATION GUIDELINES


1. HANDLE PANELS WITH CARE.
2. YOU MUST INVENTORY PANELS UPON DELIVERY.
3. ALWAYS PROVIDE ADEQUATE SUPPORT FOR PANELS WHEN STORING THEM. STORE PANELS LAYING FLAT AND COVERED.
4. KEEP PANEL SEALANT TUBES WARM FOR BEST RESULTS IN COLD WEATHER.
5. APPLY PANEL SEALANT ALONG THE LEADING EDGE OF LUMBER BEING INSTALLED INTO PANELS.
6. USE ONLY EXTREME PANEL APPROVED PANEL SEALANT/ADHESIVE.
7. PROVIDE LEVEL AND SQUARE FOUNDATIONS OR FLOOR THAT SUPPORT BOTH SKINS OF WALL PANELS.
8. HOLD BOTTOM PLATE BACK FROM EDGE OF RIM BOARD $\frac{7}{16}$ " TO ALLOW FULL BEARING OF OSB SKINS FOR WALL PANELS.
9. DRILL $1\frac{1}{2}$ " DIAMETER ACCESS HOLES IN BOTTOM AND TOP PLATES TO ALIGN WITH ELECTRICAL WIRE CHASES IN PANELS.
10. PROVIDE ADEQUATE BRACING OF PANELS DURING INSTALLATION.
11. SWEEP DEBRIS FROM PLATE AREA PRIOR TO PANEL SEALANT AND PANEL PLACEMENT.
12. DO NOT INSTALL PANELS DIRECTLY ON CONCRETE WITHOUT A CAPILLARY BREAK. SEE FOUNDATION / SLAB DETAILS.
13. MINIMUM $1\frac{1}{2}$ " BEARING ON BOTH ENDS OF ANY PANEL PLACED IN A HORIZONTAL POSITION.
14. DO NOT LIFT PANELS BY TOP SKIN.
15. DO NOT PUT PLUMBING IN EXTREME PANELS.
16. CONSULT YOUR HVAC PROFESSIONAL FOR PROPER VENTILATION AND INDOOR AIR CONTROL DESIGN OR THE BUILDING DEPARTMENT FOR LOCAL CODE COMPLIANCE.
17. READ SHOP DRAWINGS AND FULLY UNDERSTAND ALL DETAILS PRIOR TO FRAMING.
18. CONSULT YOUR BUILDING DEPARTMENT OR ARCHITECT FOR VAPOR BARRIER DESIGN.
19. STRAPS AND HOLD DOWNS MUST BE INSTALLED AS SPECIFIED BY ENGINEER.
20. ALWAYS VERIFY REQUIREMENTS IMPOSED BY THE CODE JURISDICTION OR LOCAL BUILDING DEPARTMENT.
21. FOAM ALL PENETRATIONS IN PANELS, INCLUDING ELECTRICAL BOXES.
22. A VAPOR RETARDANT IS ALWAYS REQUIRED IN COLD CLIMATE RESIDENTIAL APPLICATIONS ON WARM SIDE OF THE PANEL. IF SIP FLASHING IS USED ALONG WITH PANEL SEALANTS AT PANEL CONNECTIONS, THIS ASSEMBLY IS CONSIDERED AN ADEQUATE VAPOR RETARDANT. REFER TO PBS TECHNICAL BULLETIN #28 FOR ADDITIONAL INFORMATION.
23. FIELD CUTTING AND TRIMMING OF PANELS MAY BE REQUIRED DUE TO THE IMPERFECTIONS OF THE BUILDING MATERIALS. PANELS TEND TO GROW IN LENGTH AS THEY ARE PUT TOGETHER. FIELD MEASURE PANELS AS THEY ARE INSTALLED TO MAKE SURE CRITICAL DIMENSIONS ARE MET, FOR EXAMPLE, CENTERLINES OF WINDOWS AND STRUCTURAL BEARING POINTS.
24. EXTREME PANELS AS WITH MOST BUILDING COMPONENTS MAY BE EXPOSED TO RAIN AND OR SNOW DURING THE ERECTION OF A PROJECT. PROVIDED WATER AND ICE ARE ALLOWED TO DISSIPATE AND THE PANELS ARE DRY PRIOR TO FINISHING, INCIDENTAL EXPOSURE TO PRECIPITATION IS NOT PROBLEMATIC. IT IS STILL RECOMMENDED THAT PROLONGED WATER EXPOSURE BE MINIMIZED AND THAT WEATHER RESISTIVE MATERIALS BE PLACED OVER THE PANELS AS SOON AS POSSIBLE.
25. DO NOT UNDER ANY CONDITION, COVER TOP SIDE OF ROOF PANELS ENTIRELY WITH ANY PEEL & STICK (ICE & WATER SHIELD) MATERIAL OTHER THAN WHERE REQUIRED BY CODE.

ELECTRICAL INSTALLATION HINTS

1. USE VERTICAL CHASES WHENEVER POSSIBLE.
2. USE A REMODELER'S BOX THAT CLAMPS THE WIRE SECURELY TO THE BOX AND HAS FLANGES SO THAT THE BOX CAN BE FASTENED TO THE PANEL SKIN.
3. DO NOT CUT LONG GROOVES IN THE PANEL SKINS. (IF ABSOLUTELY NECESSARY USE A 24" DRILL AND GO FROM ONE 4" ACCESS HOLE TO ANOTHER ACCESS HOLE.)
4. USE INTERIOR STUD WALLS WHENEVER POSSIBLE. NAIL 2x BLOCKING TO THE STUD THAT ABUTS THE WALL PANEL IN ORDER TO BRING THE ELECTRICAL BOX OUT FROM THE CORNER. RATHER THAN TRYING TO BEND AROUND A 90° TURN, DRILL A LONG DIAGONAL HOLE FROM THE STUD THROUGH THE WALL PANEL AND INTO THE HORIZONTAL CHASES. WIRES WILL SLIDE MUCH EASIER THROUGH THIS CONFIGURATION.
5. PUSH ALL WIRES THROUGH A CHASE AT THE SAME TIME. WITH ELECTRICIAN'S PLIERS, FOLD AND CRIMP THE LONGEST WIRE BACK ON ITSELF ABOUT 1". USE ELECTRICAL TAPE AND COVER THAT END. STAGGER THE ENDS OF ANY ADDITIONAL WIRES AND TAPE OVER THESE. KEEP ALL WIRES FLAT WHEN TAPING TOGETHER. HAVE 8"-10" OF STRAIGHT WIRE TO SLIDE INTO THE ELECTRICAL CHASE HOLES.
6. TO GAIN ACCESS AT ELECTRICAL CHASE INTERSECTIONS USE A 4" HOLE SAW. USE A FLAT BLADE SCREWDRIVER TO PRY OUT PLUG. NAIL THE PLUG TO THE WALL FOR LATER REINSTALLATION. AFTER ALL WIRES ARE PULLED, SPRAY FOAM THE HOLE AND REPLACE THE PLUG.
7. AVOID HORIZONTAL RUNS BETWEEN OUTLETS AND SWITCHES UNLESS THE DISTANCE IS SHORT (3' OR LESS) OR THERE ARE NO OTHER OPTIONS. IT IS USUALLY QUICKER AND MORE ECONOMICAL TO USE THE VERTICAL CHASES TO GO INTO FLOOR AND ROOF SYSTEM.

SECTION 1

GENERAL DETAILS



SECTION
NOT TO SCALE

DETAIL TITLE : BUILDING SECTION

DETAIL NO. : EP-101


PAGE NO. : 1 - 1

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : BUILDING SECTION

DETAIL NO. : EP-102

PAGE NO. : 1 - 2


UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW




ASSEMBLED VIEW

SECTION
NOT TO SCALE

DETAIL TITLE : BLOCK SPLINE CONNECTION (STD)
DETAIL NO. : EP-103
PAGE NO. : 1 - 3
UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW



SECTION
NOT TO SCALE

DETAIL TITLE : I-JOIST SPLINE CONNECTION


DETAIL NO. : EP-104

PAGE NO. : 1 - 4

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW



SECTION
NOT TO SCALE

DETAIL TITLE : DOUBLE 2x LUMBER CONNECTION


DETAIL NO. : EP-105

PAGE NO. : 1 - 5

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW



ASSEMBLED VIEW

SECTION
NOT TO SCALE

DETAIL TITLE : PLYWOOD SPLINE CONNECTION


DETAIL NO. : EP-106

PAGE NO. : 1 - 6

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW



NOTE: THIS DETAIL USED IN SITUATIONS WHERE THE SPLINE CONNECTION ON THE WARM SIDE OF THE PANELS IS NOT ACCESSIBLE

ASSEMBLED VIEW

SECTION
NOT TO SCALE

DETAIL TITLE : BLOCK SPLINE (VAPOR RETARDER)


DETAIL NO. : EP-107

PAGE NO. : 1 - 7

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW



SECTION
NOT TO SCALE

DETAIL TITLE : SPLINE FASTENED AT TOP ONLY

DETAIL NO. : EP-108


PAGE NO. : 1 - 8

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : PANEL TO STEEL CONNECTION

DETAIL NO. : EP-109


PAGE NO. : 1 - 9

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : TOP AND SILL PLATE CONNECTIONS

DETAIL NO. : EP-110


PAGE NO. : 1 - 10

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

3" CONST. LAGS @ 24" O.C.
OR 16d NAILS @ 12" O.C.
IN 2 ROWS STAGGERED
U.N.O.

STANDARD 2x LUMBER, OSB
RIMBOARD OR LVL MATERIAL RIPPED
TO OVERALL WIDTH OF PANEL. MAY
BE USED TO INCREASE WALL HEIGHT
OR TO INCREASE POINT LOADING
CAPACITY. SEE POINT LOAD CHART.




THE FOAM IS HELD BACK 1 1/2" TO
ALLOW THE TOP PLATE TO SIT FLUSH
WITH THE TOP OF THE PANEL

1 1/2" SCREWS @ 8" O.C. OR 2"-8d NAILS
@ 6" O.C. BOTH SIDES, TOP AND
BOTTOM (U.N.O.)

EXTREME PANEL WALL

PANEL HEIGHT VARIES



SLIDE
PANEL
DOWN

CONTINUOUS 3/8" x 1/2" PANEL
SEALANT IS TO BE APPLIED TO
THE TOP AND BOTH SIDES OF
THE TOP AND SILL PLATES AND
BETWEEN TOP PLATE AND TOP
SHIM PLATE

SILL PLATE IS TO BE FASTENED IN PLACE W/ 3" CONST.
LAGS @ 24" O.C. OR 16d NAILS @ 12" O.C. IN 2
ROWS STAGGERED BEFORE PANEL INSTALLATION

SECTION
NOT TO SCALE

DETAIL TITLE : TOP SHIM PLATE CONNECTION

DETAIL NO. : EP-111

PAGE NO. : 1 - 11

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW
(WITHOUT TOP PLATES)

CONTINUOUS $\frac{3}{8}$ " & $\frac{1}{2}$ "
PANEL SEALANT ON
EACH SIDE OF LUMBER
ON EACH PANEL

1 $\frac{1}{2}$ " SCREWS @ 8"
O.C. OR 2"-8d NAILS
@ 6" O.C. BOTH
SIDES, TOP AND
BOTTOM (U.N.O.)

PANEL SCREWS
W/ WASHERS @
12" O.C. (U.N.O.)

OPTIONAL
FACTORY
INSTALLED
ELECTRICAL
CHASE

EXTREME WALL
PANEL

$\frac{7}{16}$ " OSB SKINS ON
BOTH SIDES, TYPICAL

EXPANDED
POLYSTYRENE CORE

ASSEMBLED VIEW

TOP PLATES

SCREW OR NAIL THE
TOP PLATE TO THE
VERTICAL STUD WITH
(2) 3" CONST. LAGS
OR
(3) 16d NAILS

PRE-DRILL TOP AND
SILL PLATES AT
ELECTRICAL CHASE
LOCATIONS BEFORE
PLATES ARE INSTALLED

SECTION
NOT TO SCALE

DETAIL TITLE : BUTT CORNER CONNECTION (STD)

DETAIL NO. : EP-112

PAGE NO. : 1 - 12

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

PRE-ASSEMBLED VIEW
(WITHOUT TOP PLATES)

1 1/2" SCREWS OR
2"-8d NAILS @ 12"
O.C. IN 2 ROWS
STAGGERED

CONTINUOUS 3/8" & 1/2"
PANEL SEALANT ON
EACH SIDE OF
LUMBER ON EACH
PANEL

1 1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6"
O.C. BOTH SIDES, TOP
AND BOTTOM (U.N.O.)

PANEL SCREWS
W/ WASHERS @
12" O.C. (U.N.O.)

OPTIONAL
FACTORY
INSTALLED
ELECTRICAL
CHASE

EXTREME WALL
PANEL

7/16" OSB SKINS ON
BOTH SIDES, TYPICAL

EXPANDED
POLYSTYRENE CORE

ASSEMBLED VIEW

TOP PLATES

SCREW OR NAIL THE
TOP PLATE TO THE
VERTICAL STUD WITH
(2) 3" CONST. LAGS
OR
(3) 16d NAILS

PRE-DRILL TOP AND
SILL PLATES AT
ELECTRICAL CHASE
LOCATIONS BEFORE
PLATES ARE INSTALLED

SECTION
NOT TO SCALE

DETAIL TITLE : FLY-BY CORNER CONNECTION (OPT)

DETAIL NO. : EP-113

PAGE NO. : 1 - 13

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

DOUBLE 2x BEVEL SPLINES W/ 3"
CONST. LAGS @ 24" O.C. OR 16d
NAILS @ 12" O.C. IN 2 ROWS
STAGGERED W/ PANEL SEALANT
BETWEEN 2x's (U.N.O.)

PRE-ASSEMBLED VIEW
(WITHOUT TOP PLATES)

7/16" OSB SKINS ON
BOTH SIDES, TYPICAL

CONTINUOUS 3/8" x 1/2" PANEL
SEALANT ON EACH SIDE OF LUMBER
ON EACH PANEL

1 1/2" SCREWS @ 8" O.C. OR
2"-8d NAILS @ 6" O.C. BOTH
SIDES, TOP AND BOTTOM
(U.N.O.)

EXTREME WALL
PANEL

EXPANDED
POLYSTYRENE CORE

ASSEMBLED VIEW

TOP PLATES

SCREW OR NAIL THE
TOP PLATE TO THE
VERTICAL STUD WITH
(2) 3" CONST. LAGS
OR
(3) 16d NAILS

SECTION
NOT TO SCALE

DETAIL TITLE : ANGLED CORNER CONNECTION

DETAIL NO. : EP-114


PAGE NO. : 1 - 14

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.


STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : TIMBER FRAME MEMBER CONNECTION
 DETAIL NO. : EP-115
 PAGE NO. : 1 - 15
 UPDATED : MARCH 2017


Extreme Panel
 TECHNOLOGIES, INC.
 STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : TIMBER FRAME CORNER CONNECTION
 DETAIL NO. : EP-116
 PAGE NO. : 1 - 16
 UPDATED : MARCH 2017


Extreme Panel
 TECHNOLOGIES, INC.
 STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : TIMBER FRAME MEMBER CONNECTION
DETAIL NO. : EP-117
PAGE NO. : 1 - 17
UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS




SECTION
NOT TO SCALE

DETAIL TITLE : TIMBER FRAME MEMBER CONNECTION
 DETAIL NO. : EP-118
 PAGE NO. : 1 - 18
 UPDATED : MARCH 2017

Extreme Panel
 TECHNOLOGIES, INC.
 STRUCTURAL INSULATED PANELS

NOTE: STOP RIM BOARD WHERE POINT LOADS GO THROUGH



DETAIL TITLE : STRUCTURAL INSULATED RIM BOARD

DETAIL NO. : EP-119

PAGE NO. : 1 - 19

UPDATED : MARCH 2017


Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

INSTALLATION SEQUENCE:

TO ATTACH LEDGER TO WALL PANELS USE PANEL SEALANT
SPREAD EVENLY ON ENTIRE CONTACT SURFACE AND 3" CONST.
LAGS SPACED @ 12" O.C. IN 2 ROWS STAGGERED (U.N.O.) --
THEN USE PANEL SCREWS W/ WASHERS FROM OTHER SIDE OF
WALL @ 12" O.C. IN 2 ROWS STAGGERED (U.N.O.)



NOTE:
MAXIMUM 6'-0" SPAN @ 40#
LIVE LOAD.

SECTION
NOT TO SCALE

DETAIL TITLE : DECK LEDGER ATTACHMENT

DETAIL NO. : EP-120


PAGE NO. : 1 - 20

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : SILL PLATE PLACEMENT


DETAIL NO. : EP-121

PAGE NO. : 1 - 21

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

1. RECOMMENDED BRACING SHOULD BE PLACED EVERY 12'-0".
2. RECOMMENDED BRACE THICKNESS:
 - * 8'-0" TO 10'-0" PANEL - 2x4
 - * 12'-0" TO 16'-0" PANEL - 2x6
3. KEEP THE TOP 2x4x12" BLOCK WITHIN 2'-0" FROM THE TOP OF THE PANEL.
- 4.) RECOMMENDED BRACE LENGTH SHOULD BE $\frac{2}{3}$ THE HEIGHT OF THE PANEL.
- 5.) THE BRACING INSIDE AND OUTSIDE SHOULD BE LEFT ASSEMBLED UNTIL THE ROOF IS IN PLACE AND PROPERLY FASTENED.



SECTION
NOT TO SCALE

DETAIL TITLE : WIND BRACING TIPS

DETAIL NO. : EP-122

PAGE NO. : 1 - 22

UPDATED : MARCH 2017


Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

SECTION 2

FLOOR & FOUNDATION DETAILS



NOTE:
THIS DETAIL IS ONLY DESIGNED TO ILLUSTRATE THE
BASE & SILL PLATES. CONCRETE PLACEMENT AND
CONSTRUCTION PRACTICE SHOULD BE PER LOCAL
CODES.

SECTION
NOT TO SCALE


DETAIL TITLE : TREATED BASE PLATE

DETAIL NO. : EP-201

PAGE NO. : 2 - 1

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS



NOTE:

THIS DETAIL IS ONLY DESIGNED TO ILLUSTRATE THE BASE & SILL PLATES. CONCRETE PLACEMENT AND CONSTRUCTION PRACTICE SHOULD BE PER LOCAL CODES.

SECTION
NOT TO SCALE

DETAIL TITLE : TREATED SILL PLATE

DETAIL NO. : EP-202


PAGE NO. : 2 - 2

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



NOTE:

THIS DETAIL IS ONLY DESIGNED TO ILLUSTRATE THE
 BASE & SILL PLATES. CONCRETE PLACEMENT AND
 CONSTRUCTION PRACTICE SHOULD BE PER LOCAL
 CODES.

SECTION
 NOT TO SCALE

DETAIL TITLE : PANEL TO FOUNDATION CONNECTION

DETAIL NO. : EP-203


PAGE NO. : 2 - 3

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : FOUNDATION FRAMING

DETAIL NO. : EP-204

PAGE NO. : 2 - 4

UPDATED : MARCH 2017




Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

NOTE: STOP RIM BOARD WHERE POINT LOADS GO THROUGH

TOP VIEW



SECTION
NOT TO SCALE

DETAIL TITLE : INSULATED RIM BOARD CONNECTION

DETAIL NO. : EP-205


PAGE NO. : 2 - 5

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.


STRUCTURAL INSULATED PANELS




SECTION
NOT TO SCALE

DETAIL TITLE : TOP CHORD BEARING FLOOR TRUSS
 DETAIL NO. : EP-206
 PAGE NO. : 2 - 6
 UPDATED : MARCH 2017

Extreme Panel
 TECHNOLOGIES, INC.
 STRUCTURAL INSULATED PANELS



JOIST HANGERS ARE
DESIGNED TO FOLD
OVER ONTO THE TOP
OF WALL



SECTION
NOT TO SCALE

DETAIL TITLE : HANGING FLOOR SYSTEM

DETAIL NO. : EP-207

PAGE NO. : 2 - 7

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

EXTREME
WALL PANEL

FIELD INSTALLED
PANEL SILL PLATE

CONTINUOUS $\frac{3}{8}$ "
$\frac{1}{2}$ " PANEL
SEALANT

$1\frac{1}{2}$ " SCREWS @ 8"
O.C. OR 2"-8d
NAILS @ 6" O.C.
FASTENED ON
EACH SIDE (U.N.O.)

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM $1\frac{1}{4}$ "
PENETRATION INTO SILL
PLATE (U.N.O.)

OPTIONAL PANEL SCREWS

MIN. $\frac{7}{16}$ " UNDERLAYMENT
PERPENDICULAR TO
PANEL SEAMS

EXTREME FLOOR PANEL

DOUBLE TREATED 2x SILL
PLATE ATTACHED
TOGETHER W/ 3" CONST.
LAGS @ 24" O.C. OR 16d
NAILS @ 12" O.C. IN 2
ROWS STAGGERED (U.N.O.)
W/ PANEL SEALANT
BETWEEN 2x's

SILL SEALER

CONCRETE OR
MASONRY FOUNDATION

ANCHOR BOLTS
PLACED PER
CODE

SECTION
NOT TO SCALE

DETAIL TITLE : PANEL FLOOR TO FOUNDATION

DETAIL NO. : EP-208


PAGE NO. : 2 - 8

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : PANEL FLOOR BLOCKING
 DETAIL NO. : EP-209
 PAGE NO. : 2 - 9
 UPDATED : MARCH 2017

Extreme Panel
 TECHNOLOGIES, INC.
 STRUCTURAL INSULATED PANELS

EXTREME
FLOOR PANELS

1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6" O.C.
FASTENED ON EACH SIDE
(U.N.O.)

BLOCK SPLINE
(SEE DETAIL EP-103)

FULL BEARING
BLOCKING REQUIRED
UNDER POINT LOADS
(SEE DETAIL EP-209)

CONTINUOUS RIM
BETWEEN SUPPORT
MEMBERS

SECTION
NOT TO SCALE

DETAIL TITLE : PANEL FLOOR BLOCKING

DETAIL NO. : EP-210

PAGE NO. : 2 - 10

UPDATED : MARCH 2017

Extreme Panel


TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

TENSION / COMPRESSION
POST IN END OF SHEAR
WALL AS REQUIRED BY
ENGINEERING

FIELD CUT PANEL
ACCORDINGLY TO INSTALL
HOLDDOWN. FILL ANY
VOIDS W/ EPS RIGID OR 2
PART EXPANDABLE FOAM
AND REPLACE OSB SKIN

EXTREME WALL PANEL



TREATED BASE PLATE

CONCRETE WALL OR SLAB

FASTENERS AS REQUIRED
TO ATTACH HOLDDOWN
TO POST

HOLDDOWN ANCHOR
PER ENGINEERING

NOTE:
VERIFY W/ ENGINEER IF DOUBLE SILL PLATE
W/ TWO ROWS OF 1 1/2" SCREWS OR 2"-8d
NAILS @ 4" O.C. STAGGERED ON EACH
SIDE IS AN ACCEPTABLE ALTERNATE

SECTION
NOT TO SCALE

DETAIL TITLE : HOLDDOWN CONNECTION

DETAIL NO. : EP-211

PAGE NO. : 2 - 11

UPDATED : MARCH 2017


Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

NOTE:

VERIFY W/ ENGINEER IF DOUBLE SILL PLATE
W/ TWO ROWS OF 1 ½" SCREWS OR 2"-8d
NAILS @ 4" O.C. STAGGERED ON EACH
SIDE IS AN ACCEPTABLE ALTERNATE



NOTE:

METAL STRAP MAY BE ATTACHED
OVER THE OUTSIDE OF THE WALL
PANEL - USE FASTENERS THAT WILL
NOT AFFECT FINISHING OF THE WALL

SECTION
NOT TO SCALE

DETAIL TITLE : STRAP HOLDDOWN CONNECTION

DETAIL NO. : EP-212

PAGE NO. : 2 - 12

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS




NOTE: STOP RIM BOARD WHERE POINT LOADS GO THROUGH.

WHEN GABLE WALL GOES STRAIGHT THROUGH, THE FLOOR TRUSS MUST START NEXT TO THE WALL.*

STRONGBACK BRACING:

STRONGBACK, 2x6 MINIMUM, SHOULD BE SECURED TO A VERTICAL MEMBER WITH (3) 16d NAILS ON ALL FLOOR TRUSSES. FOR SPANS LESS THAN 20'-0" ONE ROW OF STRONGBACK AT THE CENTERLINE IS SUFFICIENT. FOR SPANS GREATER THAN 20'-0" USE ONE ROW OF STRONGBACK FOR EACH 10'-0" OF TRUSS SPAN. BLOCKING BEHIND THE VERTICAL IS RECOMMENDED WHILE NAILING THE STRONGBACK IN PLACE. STRONGBACK LUMBER SHOULD BE AT LEAST 14'-0" IN LENGTH AND LAPPED 2'-0" AT THERE ENDS OVER TWO ADJACENT FLOOR TRUSSES. ALWAYS FOLLOW THE FLOOR TRUSS LAYOUT FOR THE PLACEMENT OF THE BRACING AND SIZE.

FLOOR JOISTS ARE TO BE FASTENED TO TOP PLATE WITH (2) 3" CONST. LAGS OR (3) 16d NAILS. FOR PANELS RUNNING PARALLEL TO THE FLOOR JOISTS, BLOCKING SPACERS MUST BE PLACED 8'-0" O.C. THE ENTIRE LENGTH OF THE HOUSE BETWEEN THE JOISTS.



SECTION
NOT TO SCALE

DETAIL TITLE : BRACING FOR OPEN WEB FLOORING

DETAIL NO. : EP-213

PAGE NO. : 2 - 13

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

SECTION 3

WALL DETAILS


NOTE: SEE PBS DESIGN MANUAL LOAD
CHARTS FOR ALLOWABLE LOADS

CONTINUOUS TOP PLATE - SPLICES
MINIMUM 1'-0" FROM PANEL JOINTS

WINDOW OPENING W/ HEADER

LARGER OPENING REQUIRES HEADER
SIZED ACCORDING TO THE LOADS
REQUIRED FOR THE STRUCTURE

PANEL HEADER



SECTION
NOT TO SCALE

DETAIL TITLE : TYPICAL PANEL WALL

DETAIL NO. : EP-301


PAGE NO. : 3 - 1

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : TYPICAL WINDOW OPENING

DETAIL NO. : EP-302


PAGE NO. : 3 - 2

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : DOUBLE BUCK WINDOW OPENING

DETAIL NO. : EP-303

PAGE NO. : 3 - 3

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

CONTINUOUS TOP PLATE - SPLICES
MINIMUM 1'-0" FROM PANEL JOINTS

TOP SHIM PLATE

SOLID HEADER USING LVL OR
GLU-LAM SIZED ACCORDING TO
THE LOADS REQUIRED FOR THE
STRUCTURE (HEADER TO THE
TOP OF PANEL WHEN FLOOR
SYSTEM OR ROOF TRUSSES
BEAR ON WALL)

EXTREME
WALL
PANEL

KING STUD AS
REQUIRED BY ENGINEER

TRIMMERS AS
REQUIRED FOR PROPER
HEADER BEARING

LOWER WINDOW PANEL

KING STUD AS
REQUIRED BY ENGINEER

NOTE:
HEADER LOCATED AT
BOTTOM OF UPPER
WINDOW PANEL W/
PANEL ROOF

SECTION
NOT TO SCALE

DETAIL TITLE : HEADERED WINDOW OPENING

DETAIL NO. : EP-304A

PAGE NO. : 3 - 4

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.


STRUCTURAL INSULATED PANELS

CONTINUOUS TOP PLATE - SPLICES
MINIMUM 1'-0" FROM PANEL JOINTS

TOP SHIM PLATE

INSUL-BEAM II HEADER SIZED
ACCORDING TO TECHNICAL
BULLETIN #30 & THE LOADS
REQUIRED FOR THE STRUCTURE
(HEADER @ TOP OF PANEL
WHEN FLOOR SYSTEM OR
ROOF TRUSSES BEAR ON WALL)

EXTREME
WALL
PANEL



KING STUD AS
REQUIRED BY ENGINEER

TRIMMERS AS
REQUIRED FOR PROPER
HEADER BEARING

LOWER WINDOW PANEL

KING STUD AS
REQUIRED BY ENGINEER

NOTE:
HEADER LOCATED AT
BOTTOM OF UPPER
WINDOW PANEL W/
PANEL ROOF

SECTION
NOT TO SCALE

DETAIL TITLE : INSUL-BEAM II HEADERED OPENING

DETAIL NO. : EP-304B


PAGE NO. : 3 - 4b

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : ROOF TRUSS BEARING

DETAIL NO. : EP-305


PAGE NO. : 3 - 5

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

NOTES:

1. HOLES MUST BE DRILLED IN THE TOP AND BOTTOM PLATES AT THE LOCATION OF THE VERTICAL ELECTRICAL CHASES TO ALLOW ACCESS TO THE CHASE AFTER THE PANELS ARE IN PLACE. HOLES THAT ARE ON OR NEAR A TRUSS OR JOIST CAN BE DRILLED IN AT AN ANGLE TO ALLOW FOR ACCESS.
2. WITH THE EXCEPTION OF THE FACTORY INSTALLED CHASES, ALL OTHER NECESSARY ELECTRICAL HOLES ARE TO BE FIELD CUT ONSITE USING THE HOT IRON FOAM CUTTER SUPPLIED. ALSO, PLAN AHEAD FOR ELECTRICAL CHASES AROUND DOOR ROUGH OPENINGS.
3. ADDITIONAL FIELD INSTALLED ELECTRICAL CHASES MAY BE NEEDED AROUND ROUGH OPENINGS. THEY CAN BE FIELD CUT BEFORE INSTALLING DIMENSIONAL LUMBER WITH AN ELECTRIC FOAM CUTTER.
4. ALL PENETRATIONS ARE REQUIRED TO BE FOAMED IN PLACE AFTER ELECTRICAL ROUGH-IN IS DONE.
5. FOLLOW LOCAL CODE REQUIREMENTS FOR ELECTRICAL INSTALLATION.



DETAIL TITLE : ELECTRICAL CHASES

DETAIL NO. : EP-306

PAGE NO. : 3 - 6


UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

SAVE PLUG W/ OSB SKIN TO REINSTALL
AFTER WIRING IS COMPLETE USING FOAM
& PANEL SEALANT TO SEAL UP.

FIELD DRILLED TOP PLATES

EXTREME WALL PANEL



SECTION
NOT TO SCALE

DETAIL TITLE : ELECTRICAL CHASES

DETAIL NO. : EP-307


PAGE NO. : 3 - 7

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : ELECTRICAL BOX INSTALLATION

DETAIL NO. : EP-308

PAGE NO. : 3 - 8


UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

NOTE:
PLAN AHEAD FOR ELECTRICAL CHASES WHERE STANDARD
CHASES ARE NOT AVAILABLE. COMMUNICATE WITH THE
ELECTRICIAN BEFORE INSTALLING LUMBER AROUND DOORS.




SECTION
NOT TO SCALE

DETAIL TITLE : ELECTRICAL DOOR CHASES
DETAIL NO. : EP-309
PAGE NO. : 3 - 9
UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PANEL SCREWS W/
WASHERS 12" O.C. (U.N.O.)
FROM OUTSIDE INTO
INTERIOR FRAMING

EXTREME WALL PANEL



3" CONST. LAGS @ 24" O.C. IN
2 ROWS STAGGERED (U.N.O.)
USING PANEL SEALANT BETWEEN
OSB & 2x LUMBER

INTERIOR WALL FRAMING

SECTION
NOT TO SCALE

DETAIL TITLE : INTERIOR WALL TO PANEL CONNECTION


DETAIL NO. : EP-310

PAGE NO. : 3 - 10

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

EXTREME WALL PANEL



NOTE:
FASTEN CABINET TO PANELS FOLLOWING CABINET
MANUFACTURER'S RECOMMENDATIONS (FOR
HIGHER CABINET LOADS CONSULT EXTREME
PANELS TECHNOLOGIES BEFORE INSTALLATION)

SECTION
NOT TO SCALE

DETAIL TITLE : TYPICAL CABINET CONNECTION

DETAIL NO. : EP-311

PAGE NO. : 3 - 11

UPDATED : MARCH 2017

Extreme Panel


TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

INTERIOR WALL

CONNECT VENT TO OTHER VENTS
OR VENT THROUGH ROOF

EXTREME WALL PANEL



AIR GAP

CLEAN OUT

1 1/2" DIAMETER PIPE

LOCATE 90 DEGREE
ELBOW AS HIGH AS
POSSIBLE INSIDE
CABINET

NO FIXTURES UPSTREAM
(ONLY CLEAN OUT)

NOTE: CONSULT LOCAL BUILDING
CODES FOR ACCEPTANCE

SECTION
NOT TO SCALE

DETAIL TITLE : ISLAND VENT INSTALLATION

DETAIL NO. : EP-312

PAGE NO. : 3 - 12

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

Construction Detail Manual

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

SIPs Done Right!

800.977.2635
extremepanel.com




**Structural Insulated
Panel Association**

EXTREME ROOF PANEL

2x WEDGE - EACH LAYER
FASTENED TOGETHER W/
PANEL SEALANT & 3" CONST.
LAGS @ 24" O.C. IN 2
ROWS STAGGERED IN FIELD
(U.N.O.)

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM 1 1/4"
PENETRATION INTO TOP
PLATE MATERIAL
(U.N.O.)



NOTE: 2x WEDGE ONLY USED UP
THROUGH 6:12 ROOF PITCHES

SECTION
NOT TO SCALE

DETAIL TITLE : BUILT-UP 2x WEDGE

DETAIL NO. : EP-401

PAGE NO. : 4 - 1

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

EXTREME ROOF PANEL

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM 1 1/4"
PENETRATION INTO
BEVELED TOP PLATE
(U.N.O.)

EXTREME
WALL PANEL

6" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

1 1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6" O.C.
FASTENED EACH SIDE
(U.N.O.)

CONTINUOUS 3/8" # 1/2"
PANEL SEALANT
TYPICAL EACH SIDE

2x BEVELED TOP
PLATE CUT TO FIT

SECTION
NOT TO SCALE

DETAIL TITLE : BEVELED TOP PLATE

DETAIL NO. : EP-402

PAGE NO. : 4 - 2

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

EXTREME ROOF PANEL

L-SHAPED WEDGE FASTENED TOGETHER W/ PANEL SEALANT & 3" CONST. LAGS 24" O.C. OR 16d NAILS @ 12" O.C. IN 2 ROWS STAGGERED IN FIELD, THEN FILL VOID W/ 2-PART EXPANDABLE FOAM OR EPS RIGID FOAM (U.N.O.)

PANEL SCREWS W/ WASHERS @ 12" O.C. W/ MINIMUM 1/4" PENETRATION INTO TOP PLATE MATERIAL (U.N.O.)

EXTREME WALL PANEL

VOID IN FOAM TO RUN ELECTRICAL WIRE

1/2" SIP TAPE ON (WINTER) WARM SIDE OF PANEL

3" CONST. LAG @ 24" O.C. OR 16d NAILS @ 12" O.C. (U.N.O.)

1 1/2" SCREWS @ 8" O.C. OR 2"-8d NAILS @ 6" O.C. FASTENED EACH SIDE

CONTINUOUS 3/8" & 1/2" PANEL SEALANT TYPICAL EACH SIDE

SECTION
NOT TO SCALE

DETAIL TITLE : L-SHAPED 2x WEDGE

DETAIL NO. : EP-403

PAGE NO. : 4 - 3

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

EXTREME ROOF PANEL

L-SHAPED WEDGE FASTENED TOGETHER W/ PANEL SEALANT & 3" CONST. LAGS 24" O.C. OR 16d NAILS @ 12" O.C. IN FIELD, THEN FILL VOID W/ 2-PART EXPANDABLE FOAM OR EPS RIGID FOAM (BASE PLATE IS TREATED AND FASTENED TO ICF W/ ANCHOR BOLTS)

VOID IN FOAM TO RUN ELECTRICAL WIRE

ANCHOR BOLTS PLACED PER CODE

$\frac{1}{2}"$ MIN.

PANEL SCREWS W/ WASHERS @ 12" O.C. W/ MINIMUM $\frac{1}{4}"$ PENETRATION INTO TOP PLATE MATERIAL (U.N.O.)

ICF WALL

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF TO ICF CONNECTION

DETAIL NO. : EP-404

PAGE NO. : 4 - 4

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.


STRUCTURAL INSULATED PANELS

EXTREME ROOF PANEL

$\frac{3}{4}$ " GAP FILLED W/
2-PART EXPANDABLE
FOAM

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM $1\frac{1}{4}$ "
PENETRATION INTO
STRUCTURAL SUPPORT
(U.N.O.)

ROOF STRAP REQUIRED ON
PITCHES OVER 8/12.
PLACED EVERY 2'-0" O.C. &
FASTENED W/ 10d x $1\frac{1}{2}$ "
GALVANIZED NAILS. 10
NAILS PER STRAP IS
REQUIRED.



STRUCTURAL SUPPORT MINIMUM 3" WIDE
FOR MINIMUM $1\frac{1}{2}$ " BEARING FOR PANEL
ON EACH SIDE

18" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

SECTION
NOT TO SCALE

DETAIL TITLE : FLUSH FOAM RIDGE (STANDARD)

DETAIL NO. : EP-405

PAGE NO. : 4 - 5

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS


2x LUMBER IN END
OF ROOF PANEL

FIELD INSTALLED EPS
FOAM RIDGE CAP

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM 1 1/4"
PENETRATION INTO
STRUCTURAL
SUPPORT (U.N.O.)

CONTINUOUS 3/8" x 1/2"
PANEL SEALANT
TYPICAL EACH SIDE

1 1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6" O.C.
FASTENED EACH SIDE



EXTREME ROOF PANEL

SINGLE PART EXPANDABLE
FOAM OR PANEL SEALANT

STRUCTURAL SUPPORT MINIMUM 3" WIDE
FOR MINIMUM 1 1/2" BEARING FOR PANEL
ON EACH SIDE

18" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF WEDGE DETAIL

DETAIL NO. : EP-406

PAGE NO. : 4 - 6

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS


2x LUMBER IN END
OF ROOF PANEL

PANEL SCREWS W/
WASHERS @ 24" O.C.
W/ MINIMUM 1 1/4"
PENETRATION INTO 2x
LUMBER (U.N.O.)

PANEL SCREWS
W/ WASHERS @
12" O.C. W/
MINIMUM 1 1/4"
PENETRATION
INTO
STRUCTURAL
SUPPORT
(U.N.O.)

1 1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6" O.C.
FASTENED EACH SIDE

CONTINUOUS 3/8" # 1/2"
PANEL SEALANT
TYPICAL EACH SIDE



STRUCTURAL SUPPORT MINIMUM 3" WIDE
FOR MINIMUM 1 1/2" BEARING FOR PANEL
ON EACH SIDE

1 8" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

SECTION
NOT TO SCALE

DETAIL TITLE : 12:12 PITCH RIDGE

DETAIL NO. : EP-407

PAGE NO. : 4 - 7

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

PANEL SCREWS W/ WASHERS
@ 12" O.C. W/ MINIMUM 1 1/4"
PENETRATION INTO
STRUCTURAL SUPPORT
(U.N.O.)

EXTREME ROOF PANEL

VALLEY FLASHING

1 8" SIP TAPE ON
(WINTER) WARM
SIDE OF PANEL

CONTINUOUS 1/2" PANEL
SEALANT OR FILL GAPS
WITH 2-PART
EXPANDABLE FOAM AT
FOAM JOINT

STRUCTURAL SUPPORT
MINIMUM 3" WIDE FOR
MINIMUM 1 1/2" BEARING
FOR PANEL ON EACH SIDE

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF VALLEY (FLUSH FOAM)

DETAIL NO. : EP-408


PAGE NO. : 4 - 8

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : ROOF VALLEY (LUMBER CONNECTION)

DETAIL NO. : EP-409


PAGE NO. : 4 - 9

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : ROOF VALLEY (OVERLAY)

DETAIL NO. : EP-410

PAGE NO. : 4 - 10

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

PANEL SCREWS W/ WASHERS @
12" O.C. W/ MINIMUM 1/4"
PENETRATION INTO STRUCTURAL
SUPPORT (U.N.O.)

EXTREME ROOF PANEL

1 1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6"
O.C. FASTENED EACH
SIDE (U.N.O.)

VALLEY FLASHING

1/8" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

STRUCTURAL SUPPORT
MINIMUM 3" WIDE FOR
MINIMUM 1 1/2" BEARING
FOR PANEL ON EACH SIDE

CONTINUOUS 3/8" x 1/2"
PANEL SEALANT TYPICAL
EACH SIDE AND BOTH
FACES

DOUBLE BEVELED 2x OR
LVL SPLINE W/ 3" CONST.
LAGS 24" O.C. OR 16d
NAILS @ 12" O.C. IN 3
ROWS STAGGERED W/
PANEL SEALANT BETWEEN
MEMBERS (U.N.O.)

NOTE:
VALLEY CONNECTION USED IN
LARGER DORMER SITUATIONS
AND SEISMIC AREAS

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF VALLEY (LUMBER CONNECTION)

DETAIL NO. : EP-411

PAGE NO. : 4 - 11

UPDATED : MARCH 2017

Extreme Panel


TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

EXTREME ROOF PANEL

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM 1 1/4"
PENETRATION INTO
STRUCTURAL SUPPORT
(U.N.O.)

CONTINUOUS 1/2"
PANEL SEALANT OR
FILL GAPS WITH
2-PART EXPANDABLE
FOAM AT FOAM JOINT



STRUCTURAL SUPPORT MINIMUM 3" WIDE
FOR MINIMUM 1 1/2" BEARING FOR PANEL
ON EACH SIDE

1/8" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF HIP (FLUSH FOAM)

DETAIL NO. : EP-412

PAGE NO. : 4 - 12

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

CONTINUOUS $\frac{3}{8}$ " \times $\frac{1}{2}$ "
PANEL SEALANT TYPICAL
EACH SIDE AND BOTH
FACES

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM $1\frac{1}{4}$ "
PENETRATION INTO
STRUCTURAL SUPPORT
(U.N.O.)

$1\frac{1}{2}$ " SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6"
O.C. TOP AND BOTTOM
OF PANEL (U.N.O.)

EXTREME ROOF PANEL

18" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

STRUCTURAL SUPPORT MINIMUM 3" WIDE
FOR MINIMUM $1\frac{1}{2}$ " BEARING FOR PANEL
ON EACH SIDE

DOUBLE BEVELED 2x OR
LVL SPLINE W/ 3" CONST.
LAGS 24" O.C. OR 16d
NAILS @ 12" O.C. IN 3
ROWS STAGGERED W/
PANEL SEALANT BETWEEN
MEMBERS (U.N.O.)

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF HIP (LUMBER CONNECTION)

DETAIL NO. : EP-413


PAGE NO. : 4 - 13

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



NOTE: CONSULT LOAD DESIGN
CHARTS FOR MAXIMUM OVERHANG

SECTION
NOT TO SCALE

DETAIL TITLE : FULL PANEL OVERHANG (SQUARE CUT)
DETAIL NO. : EP-414
PAGE NO. : 4 - 14
UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS

EXTREME ROOF PANEL

2x, RIMBOARD, OR
LVL MATERIAL FOR
SUBFASCIA

1 1/2" SCREWS @
8" O.C. OR 2"-8d
NAILS @ 6" O.C.
TOP AND
BOTTOM OF
PANEL (U.N.O.)

6" SIP TAPE
ON (WINTER)
WARM SIDE
OF PANEL

CONTINUOUS 3/8" x 1/2"
PANEL SEALANT
TYPICAL EACH SIDE

BEVELED TOP PLATE
(SEE DETAIL EP-402)

EXTREME WALL PANEL

NOTE: CONSULT LOAD DESIGN
CHARTS FOR MAXIMUM OVERHANG

SECTION
NOT TO SCALE

DETAIL TITLE : FULL PANEL OVERHANG (PLUMB CUT)

DETAIL NO. : EP-415

PAGE NO. : 4 - 15

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

CONTINUOUS $\frac{3}{8}$ " \times $\frac{1}{2}$ "
PANEL SEALANT TYPICAL
EACH SIDE

2x SUBFASCIA

1 $\frac{1}{2}$ " SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6"
O.C. TOP AND BOTTOM
OF PANEL (U.N.O.)

1x FASCIA
BOARD BY
OTHERS

3" CONST. LAGS @ 24"
O.C. OR 16d NAILS @ 16"
O.C. TO ATTACH FASCIA
TO SUBFASCIA (U.N.O.)

BEVELED BLOCK ATTACHED TO
SUBFASCIA W/ 3" CONST. LAGS @ 24"
O.C. OR 16d NAILS @ 12" O.C.
BEFORE SUBFASCIA IS INSTALLED IN
ROOF PANEL - FINISH UNDERSIDE W/
 $\frac{7}{16}$ " OSB (U.N.O.)

NOTE: CONSULT LOAD DESIGN
CHARTS FOR MAXIMUM OVERHANG

SECTION
NOT TO SCALE

DETAIL TITLE : FULL PANEL OVERHANG (OPTIONAL)

DETAIL NO. : EP-416


PAGE NO. : 4 - 16

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



1 1/2" SCREWS @ 8" O.C. OR
2"-8d NAILS @ 6" O.C. TOP
AND BOTTOM OF SUBFASCIA
(U.N.O.)

EXTREME ROOF PANEL

2x SUBFASCIA

CONTINUOUS 3/8" x 1/2"
PANEL SEALANT
TYPICAL EACH SIDE

6" SIP TAPE ON
(WINTER) WARM
SIDE OF PANEL

2x TOP PLATE
(SEE DETAIL EP-110)

EXTREME WALL PANEL

NOTE: CONSULT LOAD DESIGN
CHARTS FOR MAXIMUM OVERHANG

SECTION
NOT TO SCALE

DETAIL TITLE : FULL PANEL RAKE OVERHANG

DETAIL NO. : EP-417

PAGE NO. : 4 - 17

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

1 1/2" SCREWS @ 8" O.C. OR 2"-8d NAILS @ 6" O.C. ALONG RAFTER TAIL (U.N.O.)

PANEL SCREWS W/ WASHERS @ 12" O.C. W/ MINIMUM 1 1/4" PENETRATION INTO TOP PLATE MATERIAL

1 1/2" SCREWS OR 2"-8d NAILS @ 12" O.C. STAGGERED IN 5/8" PLYWOOD SPLINE

7/16" OSB ROOF SHEATHING

EXTREME ROOF PANEL

2'-0"

4"

2x6 RAFTER TAIL CUT TO SPECIFIED OVERHANG LENGTH

2x RAFTER TAIL SUPPORT CUT TO FIT SPACE BETWEEN RAFTER TAIL AND BOTTOM SKIN OF ROOF PANEL ATTACHED W/ 3" CONST. LAGS OR 16d NAILS (USED W/ OVERHANGS 2'-0" AND UNDER)

USE 2-PART EXPANDABLE FOAM TO SEAL GAPS AROUND TAIL POCKET MATERIAL AFTER INSTALLATION

FACTORY REMOVED EPS FOAM VOID TO ALLOW INSERTION OF RAFTER TAIL

6" SIP TAPE ON (WINTER) WARM SIDE OF PANEL

2x BEVELED TOP PLATE (SEE DETAIL EP-402)

EXTREME WALL PANEL

NOTE:
OVERHANGS BETWEEN 2'-0" - 3'-0" MUST HAVE ADDITIONAL SUPPORT W/ 2x LOOKOUTS. OVER 3'-0" REQUIRES HEADER SUPPORT.

NOTE:
2x4 RAFTER TAILS ARE USED W/ 8 1/4" ROOF PANELS

SECTION
NOT TO SCALE

NOTE: MAXIMUM 42# LIVE LOAD

DETAIL TITLE : RAFTER TAIL EAVE

DETAIL NO. : EP-418

PAGE NO. : 4 - 18

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

PANEL SCREWS W/ WASHERS @ 12"
O.C. W/ MINIMUM 1 1/4" PENETRATION
INTO TOP PLATE MATERIAL (U.N.O.)

1 1/2" SCREWS OR
2"-8d NAILS @ 12"
O.C. STAGGERED IN
5/8" PLYWOOD SPLINE

7/16" OSB ROOF
SHEATHING

1 1/2" SCREWS @ 8" O.C.
OR 2"-8d NAILS @ 6" O.C.
ALONG RAFTER TAIL
(U.N.O.)

EXTREME ROOF PANEL

2'-0"

4"

2x6 RAFTER
TAIL CUT TO
SPECIFIED
OVERHANG
LENGTH

2x RAFTER TAIL
SUPPORT CUT TO FIT
SPACE BETWEEN
RAFTER TAIL AND
BOTTOM SKIN OF
ROOF PANEL
ATTACHED W/ 3"
CONST. LAGS OR 16d
NAILS (2'-0" MAXIMUM
OVERHANG)

USE 2-PART
EXPANDABLE FOAM TO
SEAL GAPS AROUND
TAIL POCKET MATERIAL
AFTER INSTALLATION

FACTORY REMOVED EPS
FOAM VOID TO ALLOW
INSERTION OF RAFTER TAIL

6" SIP TAPE ON (WINTER)
WARM SIDE OF PANEL

2x TOP PLATE
(SEE DETAIL EP-110)

EXTREME WALL PANEL

NOTE:
2x4 RAFTER TAILS ARE
USED W/ 8 1/4" ROOF PANELS

SECTION
NOT TO SCALE

NOTE: MAXIMUM 42# LIVE LOAD

DETAIL TITLE : RAFTER TAIL RAKE

DETAIL NO. : EP-419

PAGE NO. : 4 - 19

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS


1 1/2" SCREWS @ 8" O.C. OR
2"-8d NAILS @ 6" O.C. TOP AND
BOTTOM OF SUBFASCIA (U.N.O.)

1 1/2" SCREWS OR
2"-8d NAILS @ 12"
O.C. FASTENED IN
ROOF SHEATHING

7/16" OSB ROOF
SHEATHING

PANEL SCREWS W/
WASHERS @ 12" O.C.
W/ MINIMUM 1 1/4"
PENETRATION INTO TOP
PLATE MATERIAL (U.N.O.)

EXTREME ROOF PANEL



SECTION
NOT TO SCALE

NOTE: MAXIMUM 42# LIVE LOAD


DETAIL TITLE : RAFTER TAIL RAKE (OPTIONAL)

DETAIL NO. : EP-420

PAGE NO. : 4 - 20

UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE

DETAIL TITLE : PARAPET WALL

DETAIL NO. : EP-421


PAGE NO. : 4 - 21

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS




NOTE:
MAXIMUM 10'-0" SPAN @ 42#
LIVE LOAD.

NOTE: THIS DETAIL IS ONLY
PERMITTED WHEN DESIGNED BY A
LICENSED STRUCTURAL ENGINEER

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF LEDGER
DETAIL NO. : EP-422
PAGE NO. : 4 - 22
UPDATED : MARCH 2017

Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS



NOTE:
PROTECT EPS CORE FROM TEMPERATURES OF 160 DEGREES
FAHRENHEIT OR ABOVE. USE ZERO CLEARANCE INSULATING
MATERIAL DESIGNED FOR HIGH TEMPERATURES AS REQUIRED

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF PENETRATIONS

DETAIL NO. : EP-423


PAGE NO. : 4 - 23

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



NOTE:
ALL FLOOR / ROOF OPENINGS MUST BE APPROVED BY A LICENSED ENGINEER. FOR OPENINGS LARGER IN SIZE THAN SHOWN ABOVE OR FOR OPENINGS THAT CUT THROUGH SPLINES, ADDITIONAL FRAMING TO SUPPORT PANEL EDGES MAY BE NEEDED PER ENGINEERING REQUIREMENTS.

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF / FLOOR OPENINGS

DETAIL NO. : EP-424


PAGE NO. : 4 - 24

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS



SECTION
NOT TO SCALE


DETAIL TITLE : ROOF PANEL CONNECTION

DETAIL NO. : EP-425


PAGE NO. : 4 - 25

UPDATED : MARCH 2017


Extreme Panel
TECHNOLOGIES, INC.
STRUCTURAL INSULATED PANELS



PANELS UP TO 16'-0" LONG
REQUIRE (4) PANEL
SCREWS PER SUPPORT
FOR SINGLE AND TWO
SPAN CONDITIONS (U.N.O.)



PANELS GREATER THAN
16'-0" LONG REQUIRE (6)
PANEL SCREWS PER
SUPPORT FOR SINGLE AND
TWO SPAN CONDITIONS
(U.N.O.)



PANELS ANY LENGTH W/
MULTIPLE SPAN CONDITIONS
REQUIRE (4) PANEL SCREWS
PER SUPPORT (U.N.O.)

NOTE: ILLUSTRATED PANELS ARE
4'-0" WIDE (FOR 8'-0" WIDE PANELS
DOUBLE QUANTITIES OF FASTENERS)

SECTION
NOT TO SCALE

DETAIL TITLE : ROOF / FLOOR FASTENING PATTERNS

DETAIL NO. : EP-426

PAGE NO. : 4 - 26

UPDATED : MARCH 2017

Extreme Panel

TECHNOLOGIES, INC.

STRUCTURAL INSULATED PANELS

SECTION 5

SUPPLEMENTAL INSERTS

Instructions for Applying Two-Part Expanding Foam Sealant

Our foam sealant is a two-part expanding polyurethane foam with high expansion and quick curing. A typical curing time for expanding foam sealant is between 3 and 4 minutes, depending on the temperature. The units are self-contained in the sense that no other components are required for the foam to expand and cure. The chemistry of the foam formation is sensitive to temperature and the ratio in which the two parts are combined. When the foam expands and sets properly, it is a high density and high R-value foam which will adequately prevent the flow of air through any voids in the panels insulation or connections of panels together to minimize the chance for air & moisture to be transported through these areas. Examples of these areas are ridge, valley, & eave connections.

The following is a list of hints and suggestions that supplement the manufacturer's instructions for successful use of this product.

- 1) A vinyl tube can be added to the end of the tip to assist in reaching hard-to-reach places such as the bottom of ridge cuts. Suitable hose can be purchased at any reasonable hardware store. Hoses are reusable and transferable from one kit to the next, even after several months provided that the hose either remains attached to a tank or is suitably plugged to prevent air from contacting the chemicals in the hose.
- 2) Use of foam sealant in cold weather requires special care. Watch for the following:
 - 1) Cold tanks (the temperature indicator on the side of the tank shows the temperature of the contents of the tank, not ambient air temperature.) For best results, the tank contents should be at 75 F or warmer.
 - 2) Holes in the seams will need to be placed closer together.
 - 3) Foam often tends to be dry and crumbly which signifies a slightly "A" rich foam. (This is not a problem – the foam will pick up moisture from the atmosphere and soften in time.)
- 3) Apply the foam in dry conditions and to dry materials. ***DO NOT apply the foam in wet conditions or to wet materials.*** Water will cause the propellant to disintegrate and prevent proper expansion and curing.

- 4) When foaming in a ridge or valley connection, make sure to get foam applied all the way through the panels to the inside skin to make sure all voids are filled adequately.
- 5) To foam in an eave detail like the L-Shaped Wedge, after the panels are installed drill holes every 12"-18" through the 2x material making sure to take special care if any electrical wiring was run in the void behind the wedge. Then fill every other hole with foam sealant for 4-10 seconds depending on the temperature and how much foam remains in the tank. Make sure that foam comes out of the holes which had no foam placed in them. If no foam comes up the middle holes, you will need to increase the length of time that you spray the foam sealant into the holes. (Note: Make sure you do a test shot on the next tank before spraying in the seam.)
- 6) If it is required to foam seams in the panels, first drill holes to the foam chase 12-18" apart over the whole roof prior to starting to foam. Then fill every other hole with foam sealant for 4-10 seconds depending on the temperature and how much foam remains in the tank. Make sure that foam comes out of the holes which had no foam placed in them. If no foam comes up the middle holes, you will need to increase the length of time that you spray the foam sealant into the holes. After the foam has cured, go back and drill new holes in the locations where no foam came up the middle holes and drill new holes to determine the extent of the foam sealant and then re-foam to fill any voids. If you think the foam has not set up in the seam, drill test holes along the seam to determine if it has or not. If the foam has completely collapsed, new foam can be put in the existing holes. (Note: Make sure you do a test shot on the next tank before spraying in the seam.) Methodically foam each seam so every seam on both sides of the spline and every open seam is adequately foamed.

OPERATING INSTRUCTIONS

English

FROTH-PAK™ Polyurethane Foam System

WARNING


Before using *Froth-Pak*™ polyurethane foam, please read and follow the instructions on this sheet.

CONTENTS

HCFC Complete Kit of *Froth-Pak* polyurethane foam

- 2 Steel tanks of *Froth-Pak* foam (1 iso, 1 polyol)
- 1 *Insta-Flo*™ dispenser and hose assembly
- 1 assortment Anti-Crossover Nozzles
- 1 Petroleum jelly packet (5g)
- 1 Operating instruction sheet
- 1 Wrench 5/8" (*Froth-Pak* 600 kit only)

PERSONAL PROTECTION



ALWAYS WEAR PROTECTIVE EYEWEAR, GLOVES, AND CLOTHING WHEN OPERATING.


USE ONLY WITH ADEQUATE VENTILATION OR APPROPRIATE RESPIRATORY EQUIPMENT.

GETTING THE KIT READY


- 1) This instruction sheet is packed in a reusable bag with an assortment of Anti-Crossover Nozzles, and a petroleum jelly packet (5g). The *Insta-Flo* dispenser and hose assembly is connected to the chemical tanks. Lift the *Insta-Flo* dispenser and hose assembly from the box and fully uncoil hose.
- 2) Free the perforated section in upper section of the box (near the locking tab that retained the lid), and bend it down to allow the hoses to enter into the two cutouts provided.



- 3) Apply a coating of petroleum jelly to the inside face of the *Insta-Flo* dispenser. This makes cleaning of the dispenser face much easier and extends the effective life of the *Insta-Flo* dispenser.




- 4) **For users of *Froth-Pak* 600 polyurethane foam.** Using the wrench provided, tighten the hose assemblies for both "A" and "B" valves until both are tight. The enclosed wrench is intentionally designed to warp or bend if excessive pressure is applied.



- 5) Turn the tank valves on fully, noting the initial movement of chemical through the clear hoses as a confirmation of flow.



- 6) Purge the system into a waste container by activating the trigger of the *Insta-Flo* dispenser. When streams are equal, release the trigger, clean the chemical from the dispenser face with a clean rag, and reapply petroleum jelly.



- 7) Select either a clear (caulking) or blue (spray) Anti-Crossover Nozzle. Insert it firmly into the front of the *Insta-Flo* dispenser. Be sure the dispenser clips the nozzle firmly in place.

USING THE KIT

Like all foam kits, replace nozzle when nozzle has not been used for more than 30 seconds. Nozzle is removed by firmly depressing the yellow ejector located on the top of the *Insta-Flo* dispenser.

Before applying foam, make a small test shot into waste container to verify foam quality.

- 1) Hold the *Insta-Flo* dispenser about 6" – 24" (15 cm – 60 cm) away from the area you intend to spray. Apply foam by squeezing trigger. Note yellow safety on the trigger must be depressed first, unlocking trigger. Move the *Insta-Flo* dispenser with a steady back and forth motion when dispensing foam.
- 2) Foam will expand and will be tack free within 60 seconds (3 – 4 minutes for slow rise formulas), and is fully cured in five minutes. It is recommended that foam be applied in layers of 2" or less in any single application layer.

Note: If the foam is to be injected into a hidden cavity, a test shot is recommended prior to each injection.

TEMPERATURE

The temperature indicator on the side of the tank shows the temperature of the contents of the tank, not ambient air temperature. For best results the tank contents should be at 75° F (24° C) or warmer. *Froth-Pak* polyurethane foam can be applied effectively in cold air temperatures or on cool work surfaces (above freezing) provided the kit contents are at least 75° F (24° C).

DISPOSAL

The cylinders should have all pressure vented and all the material removed to be considered empty cylinders. **DO NOT PUNCTURE THE CYLINDERS TO RELIEVE THE PRESSURE.**

The cured foam and the empty cylinders may be disposed of as a non-hazardous waste in accordance with state and local regulations. Landfilling may have special requirements depending on local regulations. These regulations should be reviewed to insure compliance. Do not dispose of pressurized tanks.

OPERATING INSTRUCTIONS

English

TROUBLESHOOTING

If your spray pattern becomes noticeably different (i.e. cone spray changes to stream), this may be caused by dispensing foam with a used nozzle. Always inspect a nozzle prior to dispensing to make sure you have an unused nozzle mounted in the *Insta-Flo* dispenser.

If the foam or spray pattern does not react properly, replacing the nozzle will usually correct the problem. If the problem persists, remove the nozzle and carefully activate the dispenser into a waste container. Two chemical streams of approximately equal volume should flow. If streams are unequal a blockage has occurred. Shut off the tank valve on the side that is flowing properly and activate the trigger full force for 15 seconds. Once the blockage is freed turn off all tank valves. Clean any chemical from the face of the *Insta-Flo* dispenser with a clean rag and reapply petroleum jelly. Insert an unused nozzle, open all valves and dispense a test shot into a waste container. After curing check the foam quality.

If problems still occur, stop foaming.


Turn off chemical tank valves, eject the used nozzle, and release chemical line pressure by activating the dispenser into a waste container. Slowly loosen the hose connections at the tank valves. Clean chemical from the threads and replace with a new *Insta-Flo* dispenser/hose assembly. If the replacement of the *Insta-Flo* Dispenser/Hose Assembly does not solve the problem, please contact our technical staff at 800-868-1183. Note: A variety of foam dispensing nozzles are available with alternative spray patterns and various dispensing rates.

To prevent hoses from clogging, if your dispenser has not been used for one week or longer, activate the system for a few seconds by turning on the tank valves and squeezing the trigger fully without nozzle to dispense twin streams into a waste container. This will clear and repressurize the hoses and should be done every week when the system is idle. Reapply petroleum jelly and reinsert used nozzle for storage.

STORAGE

Store the *Froth-Pak* polyurethane foam system at 75° F (24° C), in a clean dry area. **DO NOT STORE AT TEMPERATURES ABOVE 120° F (49° C).** Avoid prolonged storage in direct sunlight or near heat sources. Store a partially used kit with the safety ON (do not tie

INSTA-FLO™ DISPENSER



trigger down) and valves CLOSED. Remove used nozzle, reapply petroleum jelly to face of *Insta-Flo* dispenser, and reinsert the used nozzle. Do not bleed pressure off hoses during storage. See Troubleshooting above.

WEAR PROTECTIVE EYEWEAR, GLOVES AND PROTECTIVE CLOTHING.

**24 HOUR EMERGENCY PHONE
(989) 636-4400.**

FOAM QUALITY

If friable or brittle, the foam is iso rich, and a partial blockage of the polyol side exists. Clear the blockage from the polyol side. (See Troubleshooting.)

If foam remains soft or mushy, the foam is polyol rich and a partial blockage of the iso side exists. Clear the blockage from the iso side. (See Troubleshooting.)

FIRST AID

Irritating to eyes, skin, and respiratory tract. May cause sensitization by skin contact and/or inhalation. Use in a well-ventilated area or wear a self-contained breathing apparatus. Call for Material Safety Data Sheet for additional information.

EYE: Flush with water for 15 minutes.

SKIN: Remove contaminated clothing; wash skin with soap and water.

INHALATION: Remove to fresh air.

INGESTION: Give large quantities of liquids.
DO NOT INDUCE VOMITING.

In ALL FIRST AID cases, CONSULT A PHYSICIAN.

KEEP OUT OF THE REACH OF CHILDREN.



THE DOW CHEMICAL COMPANY
1881 West Oak Parkway
Marietta, Ga 30062

Order/Inquiries: 800.366.4740
Fax: 800.326.1054
Technical Support: 888.868.1183

www.polyurethanesystems.com
* Trademark of THE DOW CHEMICAL COMPANY
Made in U.S.A. Rev. 11/02 170458



Engineering & Technical Services Inc.

Duane Boice P.E.
President

November 13, 2007

Extreme Panel Technologies, Inc.
475 E. 4th Street N.
PO Box 435
Cottonwood, MN 56229

Attention: Terry Dieken


Reference: 5/16"x 3 1/8" GRK RSS fasteners vs. #9 x 3" GRABBER fasteners

Terry,

Based on the pullout data provided by each company, the 5/16"x 3 1/8" GRK RSS fasteners may be spaced at 12" O.C. to replace the #9 x 3" GRABBER fasteners at 6" O.C.


Our engineers are available for further consultation as may be required.

With regards,


Curtis Smith, E.I.
Staff Engineer
Engineering & Technical Services

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

Duane D. Boice

Signature: 

Date: 11-13-07 License # 19015