



CONTINUOUS TENSION /
COMPRESSION POST IN
END OF SHEAR WALL PER
PLAN.

REMOVE EPS WHERE IT WILL INTERFERE
WITH THE INSTALLED HDU IN ADJACENT SIP.
FILL CAVITY WITH RIGID OR EXPANDABLE
FOAM, APPLY SEALANT PER EPT-103 AND
INSTALL SIP OVER INSTALLED HDU.

FASTENERS PER
HOLDOWN
MANUFACTURER.

HOLDOWN
ANCHOR PER PLAN

BOTTOM PLATE

TREATED SILL PLATE

CONCRETE WALL OR SLAB

N.T.S.

Rev: 12/10/2021

EPT-306A

HDU TYPE HOLDOWN
INSTALLED PRIOR TO SIP

